

UKR Shkodër - EUR 19.5 million WPIP / MIP V investment measures



Drinking Water Supply



- Rehabilitation and replacement of **53.7 km distribution network** which was outdated and heavily leaking, also through numerous illegal connections.
- **1820 new house connections with 2500 individual water meters**
- Improvement of supply pressure through construction of about **4 km of new transmission main pipeline**
- Rehabilitation and installation of 11 new flow-meters (EFM) and dataloggers with intern battery and GSM modem



Waste Water System

- Upgrade of the **Main Pumping Station Shkodra (MPS)**
- Construction of **Waste Water Treatment Plant (WWTP) Shkodra** for about 82,500 PE (Person Equivalents)
- Construction of new **5 km wastewater pipeline** from MPS to the WWTP crossing the Buna River

